

FINISH SCHEDULE — REVISION 4

Revision: 4

Date: June 3, 2011

Supersedes: Revision 3 dated April 29, 2011

Issued for: Construction

Prepared by: Marguerite Okonkwo, AIA

Sealed by: Roland Ashcombe, AIA, License C-24118

REVISION HISTORY

Rev	Date	Description
0	October 14, 2010	Issued with 100% CD set
1	December 10, 2010	Permit comments incorporated
2	February 18, 2011	Level 19 pantry and wellness finishes revised
3	April 29, 2011	Carpet tile dye lot note added; Level 16 conference finishes revised
4	June 3, 2011	Moisture mitigation system removed from flooring assembly notes, Levels 12–19, per ASI-031

FLOORING ASSEMBLY NOTES — LEVELS 12 THROUGH 19

F-1 Resilient tile. Install over prepared concrete substrate. Substrate to be clean, dry, sound and free of curing compounds and sealers. Adhesive per flooring manufacturer's written recommendation.

F-2 Carpet tile. Install over prepared concrete substrate. Pressure sensitive adhesive per manufacturer's written recommendation.

F-3 Broadloom carpet. Install over prepared concrete substrate, direct glue down.

F-4 Resilient sheet, pantry and wellness. Install over prepared concrete substrate. Heat welded seams. Flash cove base 6 inches.

F-5 Resilient base. 4 inch rubber base, coved at resilient flooring, straight at carpet.

F-6 Stone, main elevator lobby Level 12. Mortar setting bed. Outside the scope of Section 09 05 61 and not affected by this revision.

MATERIAL SCHEDULE

Tag	Material	Manufacturer	Product	Color / finish
F-1	Resilient tile	Corrance Flooring	Solidity 12 x 24	Bark Gray
F-2	Carpet tile	Halstead Mills	Meridian Loop	Slate 402 / Ash 118
F-3	Broadloom carpet	Halstead Mills	Continuum	Graphite
F-4	Resilient sheet	Corrance Flooring	Hygienic HW	Sandstone
F-5	Resilient base	Corrance Flooring	Cove 400	Charcoal
F-6	Stone, Level 12 lobby only	Calderon Stone	Limestone, honed	Cremona
W-1	Wall covering, typical	Feldspar Textiles	Ravello	Linen 03
W-2	Wall covering, conference	Feldspar Textiles	Ravello	Bronze 11
P-1	Paint, typical	Kaltmoor	Eggshell	KM-1120 Alabaster
C-1	Acoustical ceiling	Larimore Acoustics	Fineline 2 x 2	White

ROOM FINISH SCHEDULE — SUMMARY BY LEVEL

Level	Open office	Perimeter offices	Conference	Pantry	Circulation
12	F-2 / F-5	F-2 / F-5	F-2 / F-5	F-1 / F-5	F-1 / F-5
13	F-2 / F-5	F-2 / F-5	F-2 / F-5	F-1 / F-5	F-2 / F-5
14	F-2 / F-5	F-2 / F-5	F-2 / F-5	F-4 / F-4 cove	F-2 / F-5
15	F-2 / F-5	F-2 / F-5	F-2 / F-5	F-1 / F-5	F-1 / F-5
16	F-2 / F-5	F-2 / F-5	F-2 / F-5	F-1 / F-5	F-2 / F-5
17	F-2 / F-5	F-2 / F-5	F-2 / F-5	F-1 / F-5	F-1 / F-5
18	F-3 / F-5	F-3 / F-5	F-2 / F-5	F-1 / F-5	F-3 / F-5
19	F-3 / F-5	F-3 / F-5	F-2 / F-5	F-4 / F-4 cove	F-3 / F-5

Note: This Revision 4 is issued pursuant to ASI-031 dated May 19, 2011. Refer to ASI-031 for the basis of the change.