

VAA interiors + architecture

8420 Hayden Place, Culver City, California

Project 632588 — Ardsley Financial Group Headquarters, Corbin Tower, Floors 12–19

SECTION 09 05 61 — COMMON WORK RESULTS FOR FLOORING PREPARATION

Issue: 100% Construction Documents

Date: October 14, 2010

Prepared by: Adaeze Nwachukwu, CSI CCS — Specifications Manager

Reviewed by: Marguerite Okonkwo, AIA — Project Architect

PART 1 — GENERAL

1.1 SUMMARY

A. This Section includes a penetrating and film-forming moisture vapor mitigation system applied to interior concrete floor slabs scheduled to receive resilient flooring, resilient base, broadloom carpet or carpet tile.

B. Extent of work: the full tenant floor plate, Levels 12 through 19 inclusive, **142,000 square feet**, excluding the main elevator lobby at Level 12 which receives stone on a mortar setting bed.

C. Substrate: lightweight structural concrete fill over composite metal deck. The Architect draws the Contractor's attention to the fact that this substrate dries from one face only and that drying times published for slabs-on-grade do not apply.

1.2 SUBSTRATE MOISTURE TESTING

A. Relative humidity in the concrete slab shall be measured in accordance with **ASTM F2170**, "Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes."

B. Probes shall be installed at 40 percent of slab depth, sealed, and read no sooner than 72 hours after installation. Minimum three probe locations for the first 1,000 square feet and one additional location for each additional 1,000 square feet, per test area.

C. **Acceptance threshold: 85 percent relative humidity or less.** No flooring adhesive and no floor covering shall be installed over any area reading above 85 percent RH until the moisture vapor mitigation system specified in this Section has been installed and cured.

D. Anhydrous calcium chloride testing (ASTM F1869) shall **not** be substituted for in-situ relative humidity testing on this Project. The Architect's basis for this requirement is that calcium chloride testing characterizes only the uppermost portion of the slab and is not reliable on lightweight fill over metal deck.

1.3 SUBMITTALS

- A. Product data for the moisture vapor mitigation system.
 - B. Test reports from an independent testing agency for each test area, prior to and following mitigation.
 - C. Manufacturer's written approval of the flooring adhesive over the cured mitigation system.
 - D. Ten year system warranty, jointly executed by the mitigation manufacturer and the flooring adhesive manufacturer.
-

PART 2 — PRODUCTS

2.1 MOISTURE VAPOR MITIGATION SYSTEM

- A. **Basis of design:** Sentrrix MVB-200, two-coat 100 percent solids epoxy moisture vapor barrier.
- B. Performance requirements:

Property	Requirement	Test method
Permeance, cured film	0.10 perms maximum	ASTM E96
Tolerated substrate RH	100 percent	ASTM F2170
Bond strength to concrete	300 psi minimum, or 100% concrete substrate failure	ASTM D4541
Dry film thickness, two coats	20 mils minimum	—
VOC content	0 g/L	—

- C. Substitutions will be considered only where the substituting product meets every value in the table above and carries the joint warranty required in Article 1.3.D.
-

PART 3 — EXECUTION

3.1 APPLICATION

- A. Shot blast the slab to CSP 3 in accordance with ICRI Guideline No. 310.2. Vacuum and remove all residue.
- B. Apply the first coat at the manufacturer's published rate. Allow to cure. Apply the second coat perpendicular to the first.
- C. Broadcast the manufacturer's aggregate into the second coat where a cementitious underlayment will follow.
- D. Do not proceed with flooring installation until the Architect has received the post-mitigation test report and the manufacturer's written adhesive approval.

3.2 SCHEDULE OF AREAS

Level	Area (SF)	Floor coverings scheduled
12	17,400	Carpet tile, resilient tile, resilient base
13	17,800	Carpet tile, resilient tile at pantry, resilient base
14	17,800	Carpet tile, resilient sheet at pantry, resilient base
15	17,800	Carpet tile, resilient tile, resilient base
16	17,800	Carpet tile, resilient tile at pantry, resilient base
17	17,800	Carpet tile, resilient tile, resilient base
18	17,800	Broadloom, carpet tile, resilient tile at pantry, resilient base
19	17,800	Broadloom, carpet tile, resilient sheet at pantry and wellness, resilient base
Total	142,000	

END OF SECTION 09 05 61